

कुमाऊँ विश्वविद्यालय, नैनीताल

पत्रांक:केयू/वि०नियो०/८७०

दिनांक:- 21/10/2024

निविदा सूचना

अधोलिखित अनुरक्षण/मरम्मत कार्य के लिए विश्वविद्यालय में पंजीकृत ठेकेदारों से दिनांक 05.11.2024 समय अपराह्न 1:00 बजे तक निविदाएं डाक/दस्ती/कोरियर/ निविदा बॉक्स के माध्यम से आमंत्रित की जाती हैं, जो उसी दिन अपराह्न 2:00 बजे विश्वविद्यालय कार्यालय में खोले जायेंगे। निविदादाता अथवा उनके प्रतिनिधि निविदा खोलते समय उपस्थित रह सकते हैं। निविदा खोलने की तिथि में अवकाश होने पर निविदा अगले कार्य दिवस में खोले जायेंगे। विस्तृत जानकारी एवं निविदा फार्म विश्वविद्यालय की वेबसाइट www.kunainital.ac.in से अपलोड की जा सकती है।

क्र०सं०	कार्य का नाम	अनुमानित लागत	धरोहर राशि	निविदा फार्म मूल्य	कार्य पूर्ण करने की अवधि
1.	प्रशासनिक भवन में छत एवं अन्य मरम्मत कार्य।	रु० 4.78.00	रु० 10,000.00	रु० 590.00	30 दिन

कुलसचिव

कुमाऊँ विश्वविद्यालय, नैनीताल

प्रतिलिपि:-निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

1. निजी सचिव कुलपति को मा० कुलपति जी के अवलोकनार्थ।
2. कम्प्यूटर प्रोग्रामर, कु०वि०वि० को उक्त सूचना विश्वविद्यालय वेबसाइट में अपलोड करने हेतु।
3. विश्वविद्यालय में पंजीकृत ठेकेदारों को ई-मेल के माध्यम से सूचनार्थ प्रेषित।
4. सूचना पट्ट, प्रशासनिक भवन, कुमाऊँ विश्वविद्यालय, नैनीताल।

कुलसचिव

कुमाऊँ विश्वविद्यालय, नैनीताल

कुमाऊँ विश्वविद्यालय, नैनीताल

निविदा प्रपत्र

1. प्रत्येक कार्य हेतु पृथक-पृथक निविदा फार्म सीलबन्द लिफाफे में अधोहस्ताक्षरी के कार्यालय में निर्धारित तिथि एवं समय तक दस्ती/डाक/कोरियर/निविदा बॉक्स में डाली जानी आवश्यक होगी।
2. प्रत्येक निविदा के साथ रू0 100.00 का नॉन ज्यूडिशियल स्टाम्प पर एक रूप्ये का हस्ताक्षरयुक्त रसीदी टिकट संलग्न होना चाहिए।
3. प्रत्येक निविदा के साथ निर्धारित धरोहर राशि एफ0डी0आर0/एन0एस0सी0 के रूप में वित्त नियंत्रक, कुमाऊँ विश्वविद्यालय, नैनीताल के पक्ष में बन्धक बनाकर संलग्न करनी होगी।
4. निविदा फार्म निर्धारित शुल्क में लेखा अनुभाग से या वित्त नियन्त्रक के पदनाम से डिमांड ड्राफ्ट बनाकर प्राप्त किये जा सकते हैं।
5. निविदादाता को चाहिए कि वे निविदा देने से पूर्व कार्यस्थल का निरीक्षण कर लें।
6. समस्त कार्य लोक निर्माण विभाग द्वारा समय-समय पर निर्गत निर्धारित मानकों/शर्तों के अनुरूप सम्पादित किये जायेंगे।
7. किसी एक/समस्त निविदा को स्वीकृत/अस्वीकृत करने का अधिकार अधोहस्ताक्षरी के पास सुरक्षित होगा।



कुलसचिव Registrar

कुमाऊँ विश्वविद्यालय, नैनीताल
NAINITAL

Kumoan University Nainital

Tender form

Name of work- Repair of old roofing & tarrace at administrative building K.U. Nainital.

Date of Calling tender 21-10-2024

Date of opening tender 05-11-2024

Cost of tender form- Rs. 590.00

Earnest money -Rs. 10,000.00

Time of completion- 30 Days

Validity of tender- 45 Days

S.N.	Item of work	Quantity	Unit	Estimated Rate in Rs
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. 10.25.2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	136.20	kg	172.60
2	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 12.1.1 0.63 mm thick with zinc coating not less than 275 gm/m ²	196.92	Sqm	1087.65
3	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 12.41.2 110 mm diameter	18.00	Rmt	366.05
4	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 12.4.2 0.63mm thick with zinc coating not less than 275 gm/m ²	50.00	Rmt	852.15
5	Providing and fixing 15 cm wide, 45 cm overall semi-circular plain G.S. sheet gutter with iron brackets 40x3mm size, bolts, nuts and washers etc., including making necessary connections with rain water pipes complete. 12.7.2 0.63 mm thick with zinc coating not less than 275 gm/m ²	18.00	Rmt	846.80
6	12 mm cement plaster of mix (1 cement: 6 coarse sand)	67.50	Sqm	343.65
7	20 mm cement plaster of mix (1 cement: 4 coarse sand)	236.70	Sqm	487.40
8	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used.	136.00	Rmt	22.10
9	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge.	28.00	Sqm	563.10
10	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	304.20	Sqm	54.65
11	Repairing of old leakage roof by m seal etc complete	1Job	L.S	2000.00

Note- All the work shall be carried out as per P.W.D.(D.S.R.) specification and directed by Engineer Incharge
I/We tender.....% below/above on the given Estimated rates.

Sig. of contractor
(with full address)


Registrar,
Kumoan University
NAINITAI